



Southern
Nuclear

Implementation of FLEX Operator Actions in PRA Models

Parthasarathy Chandran, Southern Nuclear Operating Company
(pchandra@southernco.com)

David L Moore, DL Moore Consulting
(dlmooreconsulting@comcast.net)

John Reddington, Empyrean Services
(jereddington@gmail.com)

Implementation of FLEX Operator Actions in PRA Models - Logistics

- Rob has been amazing to have accepted to present this paper on our behalf
- For any questions, comments or disagreements
 - Please feel free to contact us
- This presentation aims to provide the key steps used in
 - Developing a realistic model for the FLEX-related Human Failure Events (HFEs)
 - Implementation of the events using CBDTM/THERP

Implementation of FLEX Operator Actions in PRA Models - Driver

- One of the primary lessons learned from the Fukushima event
 - Understanding realistic risk drivers for the plant for a given hazard
- One way to gain insights about the realistic risk drivers
 - Building and maintaining a PRA model that reflects the as-built and as-operated plant
- In order to achieve this, PRA model needs to include implemented FLEX strategies to reflect the real drivers for
 - Core damage
 - Containment integrity
- Procedures and processes have been updated at plants to ensure plant operators and personnel can implement FLEX in any applicable accident scenario

Implementation of FLEX Operator Actions in PRA Models - Strategy

- Presentation is developed based on a work done for a BWR 4 plant with Mark I containments
- Overall FLEX strategy is divided into three stages
 - Phase 1 (from time 0 to about 10 hours)
 - Use the RCIC turbine-driven pump to maintain reactor vessel water level
 - Use the safety/relief valves to remove heat from the reactor vessel to the suppression pool
 - Use the hardened containment vent system (HCVS) to remove heat from the containment
 - Phase 2 (from 10 hours to 24 hours (or beyond))
 - Use portable pumps deployed to the intake structure area to pump river water to the Reactor Building
 - Deploy two portable diesel generators to power the 600V emergency switchgear
 - Phase 3 (beyond 24 hours)
 - Continue with the Phase 2 equipment, supplemented by offsite equipment from the NSRC
- The PRA model with FLEX only includes up to phase 2, as the plant reaches a safe and stable state with the implementation of phase 1&2 FLEX well beyond its mission time of 24 hours

Implementation of FLEX Operator Actions in PRA Models - Equipment

- Strategies depended on permanently installed equipment and portable equipment.
- Permanently installed equipment included
 - RCIC system for injection to the reactor vessel
 - Station batteries for interim power until the portable diesel generators are deployed
 - Critical instrument cabinets for power to the HCVS and vital instrumentation
 - RHR SW piping from the Intake Structure to the Reactor Building with installed connections for the portable river water pump and hoses
 - Connection boxes and switches to establish electrical power from the portable diesel generators to the emergency switchgear, including battery chargers and inverters
 - Air handling units for Main Control Room (MCR) cooling
- Portable FLEX/ELAP equipment is primarily stored in the FLEX storage facility or dome, and included
 - Redundant pumps to provide water from the river to the RHR SW piping
 - Redundant diesel generators to provide power to the emergency switchgear
 - Fans to provide ventilation for the Control Building electrical rooms
 - Hoses, cables, and miscellaneous equipment such as communication systems, portable lighting, batteries, food and water

Implementation of FLEX Operator Actions in PRA Models - Methodology

- Operator actions associated with FLEX and ELAP were evaluated in detail using the EPRI HRA Calculator
- Human error probabilities (HEPs) associated with these actions such as ones stated below were considered in the context of the SBO scenario
 - Overlapping nature of these actions
 - Minimum crew staffing and workload
 - Integrated nature of these actions
- Actions have been evaluated to ensure that the timing is based on the sequential and overlapping actions
- Plant performed a detailed staffing study as well as a validation and verification process of the strategy
- Analysis was performed with the assumption
 - Minimum staffing at the plant was initially available
 - For large external events, that the fire brigade leader and two system operators would be engaged in fire response duties for the first 3 hours
 - Emergency Response Organization (ERO) would not be staffed for the first 6 hours
- Values discussed in the presentation for HEPs are internal events type numbers

Implementation of FLEX Operator Actions in PRA Models - Sequence

- The operator actions below follows in the general flow of the FLEX timeframe
 - OPHEELAP-COG : Decision to implement the ELAP procedure
 - OPHE-DEEP-SHED : Extend the life of the station batteries
 - OPHEELAP-DEP : Depressurize to avoid the unsafe region of HCTL curve
 - OPHEELAP-DEPMAIN : Prevent depressurizing below the RCIC turbine working pressure
 - OPHEELAP-DOOR-COG : Decision to open doors to reduce heat up of the control building electrical rooms, and the MCR
 - OPHEELAP-DOOR-CB : Provide ventilation for the control building electrical rooms

Implementation of FLEX Operator Actions in PRA Models - Sequence

- OPHEELAP-DOOR-MCR : Provide ventilation for the MCR
- OPHEELAP-VENT : Maintain the suppression pool temperature such that RCIC can operate
- OPHEELAP-SWAP : Swap the suction of RCIC from CST to the suppression pool
- OPHEELPH2-PMP : Deploy the FLEX phase 2 river water pump
- OPHEELPH2-AC : Deploy the FLEX phase 2 600V portable diesel generators
- OPHEELPH2-CBHVAC : Opening the doors for the control building electrical rooms
- OPHEELPH2-MCRHVAC : FLEX river water pump to the MCR AHUs

- OPHEELAP-COG
 - HEP represents the decision to implement the ELAP procedure
 - SBO procedure directs that the ELAP procedure be implemented
 - When it has been determined that no 4KV bus can be energized
 - If 50 minutes have elapsed and no 4KV bus is energized
 - Based on the clear guidance, specific ELAP training, and validated times, this cognitive HEP was determined to be highly reliable.

Implementation of FLEX Operator Actions in PRA Models - Actions

- OPHE-DEEP-SHED
 - Extend the life of the station batteries
 - Procedures direct actions to reduce and strip loads from the DC switchgear and buses
 - Initial load shed is directed by the SBO procedure
 - ELAP procedure then directs this “deep” load shed, which also involves venting the H₂ gas from the main generator
 - Based on validated times (23 minutes) which consider
 - prior load shed
 - the cognitive action to enter the ELAP procedure
 - HEP : 2E-03

- OPHEELAP-DEP
 - As the SBO progresses, the suppression pool (SP) will start to heat up
 - Based on the procedures, the operator is instructed to depressurize to avoid the unsafe region of HCTL curve
 - A well-trained action that will take place in two steps to prevent cooling down more than 100F per hour
 - HEP : 3E-04

Implementation of FLEX Operator Actions in PRA Models - Actions

- OPHEELAP-DEPMAIN
 - To prevent depressurizing below the RCIC turbine working pressure
 - New procedures to depressurize and maintain RPV pressure within 150-300 psig
 - Such that RCIC turbine can continue to operate
 - Involves opening an SRV when the pressure reaches 300 psig
 - Closing the SRV when approaching 150 psig
 - RPV pressure is monitored closely in any accident sequence, so this is a highly reliable action
 - Additionally, if the pressure goes too low, RCIC will stop, but then the pressure will rise such that RCIC can be restarted
 - If the pressure goes too high, although the HCTL limit may be violated temporarily, no immediate damage is done, and the pressure can be reduced back into the preferred range
 - HEP : 3E-04

Implementation of FLEX Operator Actions in PRA Models - Actions

- OPHEELAP-DOOR-COG
 - ELAP procedure directs the operators to open doors to reduce heat up of the
 - Control building electrical rooms
 - MCR
 - HFE represents the cognitive portion of these two actions
 - Increasing room temperatures would be obvious to the MCR operators, and the cognitive HEP was determined to be highly reliable

Implementation of FLEX Operator Actions in PRA Models - Actions

- OPHEELAP-DOOR-CB
 - Execution actions for opening doors to provide ventilation for the control building electrical rooms are simple with procedures with maps indicating the doors to be opened
 - Based on validated times, HEP : 1E-04
- OPHEELAP-DOOR-MCR
 - Execution actions for opening doors to provide ventilation for the MCR are simple with procedures with maps indicating the doors to be opened
 - Tools and instructions are available to open the elevator doors
 - Based on validated times, HEP : 2E-04

- OPHEELAP-VENT
 - ELAP scenarios without AC power, the suppression pool will heat up since there is no heat removal from containment
 - To maintain the SP temperature such that RCIC can operate, the hardened containment vent system (HCVS) is opened to allow heat to be removed by boiling and venting
 - Action includes using an Argon cylinder to pressurize and pop the rupture disc
 - Based on validated times, HEP : 6E-04

- OPHEELAP-SWAP
 - When the CST level is reduced to 1 foot, the operator must swap the suction of RCIC to the suppression pool
 - Automatic swap has been disabled by the operator in previous actions
 - Action is simple from the MCR, and is part of normal RCIC operation, not just ELAP
 - More than 6 hours have elapsed since the seismic event, so stress is reduced
 - Based on validated times, HEP : $2E-05$

Implementation of FLEX Operator Actions in PRA Models - Actions

- OPHEELPH2-PMP
 - First major Phase 2 action for ELAP is to deploy the FLEX phase 2 river water pump
 - A redundant pump is available if the first pump is not available
 - Deployment includes following steps
 - Action starts as the routes are being cleared
 - Staging the main pump at the intake structure
 - Deploying the floating pump/suction units
 - Aligning the hoses to the RHRSW hose connections
 - Pumps must be working in about 13 hours to provide water to the MCR AHUs
 - Water is also used to start refill of the CST by 19 hours
 - Procedures include step by step instructions with photos of the connections
 - Based on validated times, HEP : 6E-04

Implementation of FLEX Operator Actions in PRA Models - Actions

- OPHEELPH2-AC
 - Second major Phase 2 action for ELAP is to deploy the FLEX phase 2 600V portable diesel generators
 - Connect them to the 600V switchgear
 - Align the switches to charge the batteries
 - One portable diesel generator feeds the Div 1 switchgear of both units, and the other portable generator feeds Div 2 of both units
 - Third portable diesel generator is also available
 - Alternate connection points and staging areas are available depending on the haul routes selected
 - FLEX timeline starts 6 hours after the initiating event, and uses 13 hours from the initiating event for completion of this action for both Div 1 and Div 2 portable diesel generators
 - Procedure is detailed, with color coded connections for the cables
 - Based on validated times, HEP : 8E-04

Implementation of FLEX Operator Actions in PRA Models - Actions

- OPHEELPH2-CBHVAC
 - Opening the doors for the control building electrical rooms will maintain acceptable temperatures for over 10 hours
 - ELAP procedures direct the operators, assisted by emergency response organization staff (ERO) to install portable FLEX fans to provide ventilation for the switchgear and inverter rooms for both units
 - Action is started 7 hours after the initiating event, and is to be completed by the 10th hour
 - Fans and cables are retrieved from the FLEX dome and staged on the ground floor of the control building
 - Procedure has a map indicating where the fans are to be placed, and the cables connected
 - Based on validated times, HEP : 2E-04

Implementation of FLEX Operator Actions in PRA Models - Actions

- OPHEELPH2-MCRHVAC
 - ELAP phase 2 cooling of the MCR depends on aligning the RHRSW lines
 - which are now being fed by the FLEX river water pump
 - to the MCR AHUs, which are normally fed by PSW
 - Connections are designed to use the FLEX hoses that are stored in the FLEX dome
 - Power for the MCR AHUs and water for the AHUs would become available in the 10 to 13-hour timeframe
 - Detailed procedure is available, and ERO staff would assist with the connections
 - Based on validated times, HEP : 3E-04

Implementation of FLEX Operator Actions in PRA Models - Summary

- Specific attention should be given to the operator actions associated with the implementation of the FLEX/ELAP strategies to the following :
 - Level of plant damage (important for external events), and time to clear routes for portable equipment deployment
 - Integrated and overlapping nature of the actions such that timing for the actions depended on earlier actions
 - Potential for spurious alarms, relay chatter, and damage to annunciator system
 - Communication systems availability
 - Quality of the procedures, especially given the potential stress
 - Training
 - Workload and minimum crew, and diversion of staff to potential fire response duties
 - Access for actions outside of the MCR